

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-00460-00-0.1

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1970
CONSERVATION DIVISION
Wichita, Kansas

1-26-70

Operator's Full Name E. K. Edmiston

Complete Address 425 First Nat'l Bank Bldg., Wichita, Kansas 67202

Lease Name Taylor Well No. 1

Location NE NW NE Sec. 27 Twp. 7 Rge. (E) (W) 19

County Rooks Total Depth 3400'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co.

Address Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 4P Day 22 Month 1 Year 1970

The above well was plugged as follows:

Total Depth 3400' 8 5/8 csg set at 190' cwc 150 sk.

4 1/2 csg set at 3400' cw 150 sk cmt.

4 1/2 csg PBTD 3372 and perf. (3181-3190)

Set 4 1/2 plug at 3100' poured sand (3090-3100) Dumped 4 sk cmt W/dump bailer. (3050-3090)

Cutoff and recovered 2000' of 4 1/2 csg.

Pumped down 8 5/8 csg with 1 1/4 sk gel W/4 sk hulls, 70 sk poz 6%, 6 sk gel, 1 sk hulls and 50 sk cmt.

(0-200) cmt (200-400) gel (400-600) cmt (600-TD) gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/26/70

INV. NO. 1301-W

Signed: [Signature]
Well Plugging Supervisor