

15-163-20116-00-80

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 3 - 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don Pratt Oil Operations

Complete Address Box 390 Hays, Kansas 67601

Lease Name Griebel Well No. 1

Location NW NW SE Sec. 17 Twp. 7 Rge. (E) (W) 19

County Reeks Total Depth 3485

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 5P Day 1 Month 10 Year 1969

The above well was plugged as follows:

Total Depth 3485' 8 5/8 csg set at 204' cwc Cmt. Mat. 50-50 poz cmt W6% total gel

5 1/2 csg set at 3474' cw 200 sk cmt.

Filled 5 1/2 csg W/sd (3450-3485) Dumped 3 sk cmt W/dump bailer. (3420-3450)

Cutoff and recovered 1800' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, 100 sk 50-50 poz cmt

6% total gel, 5 sk gel, plug and 50 sk 50-50 poz cmt 6% total gel.

Cmt. (0-200) gel (200-400) Cmt. (400-700) Gel (700-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/3/69
INV. NO. 586-4

Signed: Leo F. Massey
Well Plugging Supervisor