

<sup>NO</sup> KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-19088-00-04

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Terrel Drilling & Producing

Complete Address: 754 E Wichita St Russell, Kans

Lease Name Witmer Well No. 1

Location NW NW NW Sec. 17 Twp. 7 Rge. (E) (W) 19

County Rooks Total Depth 3472

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated: reworked hole ✓

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kansas License No. 436

Operation Completed: Hour 5PM Day 17 Month 4 Year 63

The Above well was plugged as follows:

8 5/8" 172' circulated with cement - 4 1/2" 3472' with 175 sax cement -

PB 3400' - perforated 3162' - set sand and plugs to 3100' - 3 sax cement

set with dump bailer - pulled 2186' 4 1/2" to 550 - circulated hole with

heavy gel mud ( 15 sax Gel), displaced 20 sax cement through 4 1/2" at

550', heavy mud to 170', displaced 20 sax cement through 4 1/2" at 170',

heavy mud to 35', cement 35' to bottom cellar.

Mudding and cementing by Knight Company pump truck.

APR 19 1963  
04-19-1963  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/19/63

INV. NO. 6926-u

Signed: Jedon Kelly  
Well Plugging Supervisor