

DISTRICT CONSERVATION AGENT'S REPORT

13-163-00222-00-00

OR

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 0-9

LOCATION NW NW NE

SEC. 28 TWP. 7 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Gramm _____

Operator Theodore Gore Address 400 Brown Bldg Wichita, Kans

Field _____ County Rooks

Total Depth 3472 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 195' circulated with cement - 5 1/2" at 3421' with 200

sax cement behind - P.B. to 3360', perforated 3320'

Filled with sand to 3310', set 4 sax cement with dump bailer,

pulled 2320' 5 1/4" - pumped hole full mud (50 sax Gel) pumped cementing

plug to 315' followed by 100 sax cement - cement 315' to 0'.

Mudding and Cementing by Halliburton Cementing - 400# pump pressure.

Edwin Petty

District Conservation Agent

Date 4-28-57

RECEIVED
STATE CORPORATION COMMISSION

APR 30 1957

CONSERVATION DIVISION
Wichita, Kan

4-30-57

PLUGGING
FILE SEC. 28 T. 7 R. 19W
BOOK PAGE 6 LINE 9