

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 25 1962

CONSERVATION DIVISION  
Wichita, Kansas

4-25-62

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-163-03931-00-00

File No. \_\_\_\_\_ County: \_\_\_\_\_ Rooks

Location: SW SW NW Sec. 17 Twp. 7 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 20

Name of Field: \_\_\_\_\_ Total Depth: 3608

I have this date completed supervision of plugging of:

Lease Name: Le Sage Well No. B-1

Operator's Full Name: Imperial Oil of Kansas

Complete Address: 780 4th Natl Bk Bldg Wichita, Kansas

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. 309

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 3PM Day 21 Month 4 Year 62

The above well was plugged as follows:

8 5/8" 176' circulated with cement - 5 1/2" 3608' with 150 sax cement - PB  
to 3605' - perf 3580'

Filled with sand to 3560', set 4 sax cement with dump bailer - pulled 2710'  
5 1/2" to 550', circulated hole with heavy gel mud through 5 1/2" at 550' (30 sax  
gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud to 160',  
displaced 20 sax cement through 5 1/2", heavy mud to 35', set bridge and 10  
sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: Edwin Petty  
Conservation Division Agent

Reviewed: Harold Morris  
Field Supervisor

Remarks:

INVOICED

DATE 5/9/62

INV. NO. 4888-W