

DISTRICT CONSERVATION AGENT'S REPORT

15-163-02666-06-00

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE NE NE

SEC. 28 TWP. 7 RGE. 19W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Cramm

Operator Harry Gore Address Wichita, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3422 Feet.

(Describe briefly the manner in which the well was plugged)

5 1/2" at 3381 with 150 sax cement behind, 8" at 185' circulated  
with cement - P.B. 3305' top perforations at 3284'.  
Filled with chat to 3270', set 4 sax cement with dump bailer,  
pulled 2578' 5 1/2", pumped in 50 sax mud mixed with hulls,  
pumped cementing plug to 175' followed by 50 sax cement,  
filling hole from 175' to 0' with cement.  
Cementing by Sun Cementing co.

**PLUGGING**  
FILE SEC 28 T 7 R 19W  
BOOK PAGE 111 LINE 27

[Signature]  
District Conservation Agent

Date 9-22-51

**RECEIVED**  
STATE CORPORATION COMMISSION

SEP 25 1951  
CONSERVATION DIVISION  
Wichita, Kansas

9-25-51