

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-163-21449-00-00

API NUMBER \_\_\_\_\_

LEASE NAME Lorbeer

WELL NUMBER 1

\_\_\_\_\_ Ft. from S Section Line

\_\_\_\_\_ Ft. from E Section Line

SEC. 28 TWP. 7S RGE. 19W (E) or (W)

COUNTY Rooks

Date Well Completed 1981

Plugging Commenced 10-4-99

Plugging Completed 10-7-99

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Stice Oil Company

ADDRESS 709 N. Elm Stockton, Kansas 67669

PHONE # (785) 425-7240 OPERATORS LICENSE NO. 4116

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Rich Williams (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 3358'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	329'	None
				4-1/2"	3352'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each s  
Plugged off bottom with sand to 3100' and 5 sks. cement. Shot pipe @1450' and 850'.  
pumped 100 sks. cement and 300# hulls, shot @366', pumped 100 sks. of cement and 200#  
hulls and circulated to surface. 60/40 pos. 10% gel.  
Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Stice Oil Company

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the fact  
 statements, and matters herein contained and the log of the above-described well as filed to  
 the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 OCT 18 1999

SUBSCRIBED AND SWORN TO before me this 15th day of October, 1999

[Signature]  
 Notary Public

CONSERVATION DIVISION  
 WICHITA, KS My Commission Expires: \_\_\_\_\_

IRENE HERZBERG  
 State of Kansas  
 My Appt. Exp. Aug. 24, 2001

Form C  
 Revised 05-