


15-163-02666-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

ROOKS County. Sec. 28 Twp. 7 Rge. (E) 19 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE
Lease Owner Harry Gore
Lease Name Cramm Well No. 2
Office Address 400 Brown Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 7-30-51
Application for plugging filed 19
Application for plugging approved 9-25-51 19
Plugging commenced 9-25-51 19
Plugging completed 9-25-51 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3420 3391 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	185	none
				5 1/2	3382	2590

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cement down 80', filled surface pipe with mud
Four sax of cement on top.

10-4-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harry Gore, 400 Brown Bldg., Wichita, Ks.
Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Ralph Gore (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. HARRY GORE

(Signature) BY: Ralph Gore Partner
400 Brown Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of October, 19 51

Charlotte Kletchka
Notary Public.

My commission expires June 7, 1952

PLUGGED
FILE SEC 28 TWP 7 R 19 W
BOOK PAGE 111 LINE 27

13-163-02666-00-00

COMPANY: HARRY GORE

NE-NE-NE/4 Sec. 28,
Twp. 7S, Rge. 19W,
Rooks County, Kansas.

LEASE: Cramm # 2.

Elevation: 1920 Derrick Floor.

NOTE: All meas. rotary bushings.

0	65	Lime & surface Clay
65	185	Shale
185	215	Shale
215	740	Shale
740	830	Sand
830	900	Shale
900	1100	Shale
1100	1320	Sand
1320	1400	Shale Sand, Redbed.
1400	1428	Shale, Redbed
1428	1465	Anhydrite
1465	1525	Shale
1525	1755	Shale & shells
1755	1895	Shale & lime
1895	1970	Lime
1970	2055	Lime
2055	2150	Lime & shale
2150	2225	Lime & shale
2225	2370	Lime
2370	2480	Lime & shale
2480	2560	Lime & shale
2560	2650	Lime & shale
2650	2800	Shale & lime
2800	2925	Shale & lime
2925	3010	Lime
3010	3060	Shale & lime
3060	3115	Lime
3115	3160	Lime
3160	3205	Lime
3205	3240	Lime
3240	3270	Lime
3270	3290	Lime
3290	3320	Lime
3320	3335	Lime
3335	3370	Lime
3370	3382	Conglomerate
3382	3390	Arbuckle
3391	T.D. rotary bushing meas.	

Commenced: 7-18-51
Completed: 7-30-51

CASING RECORD:

8 5/8" Surface casing Set at
185' w/135 lbs cement 1 Cucl.
By Halliburton.

5-1/2" Production string set at
3382' 7' off bottom w/150 lbs
Bulk cement by Halliburton.

D.S.T. Johnston Testing Co.

3245'-3290' Tool open at 2:40
to 3:10 A.M. Recovered 510'
Mud and trace of Oil. B.H.P.
15 min. 1420#

3241'-3290' Tool open at 6:55
to 7:55 P.M. Recovered 65' mud
180' Oil & gas cut mud. B.H.P.
15 min. 1000#.

3290'-3335' Tool open 30 min.
Recovered 20' Drilling mud.
B.H.P. 350#

Ran Schlumberger to T.D.

TOPS: Geog. Tops from Big Floor

Anhydrite	1428	Lansing-KC.	3096
Topeka	2863	Base-KC.	3327
Heebner	3067	Conglomerate	3371
Dodge	3082	Arbuckle	3380

TOTAL DEPTH 3389

STATE OF KANSAS) SS
COUNTY OF ELLIS)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Cramm #2, Located NE-NE-NE/4 Sec. 28, Twp. 7S, Rge. 19W, Rooks County, Kansas.

CONTRACTOR: Strain Drilling Company.
By J.C. Strain

Subscribed and sworn to before me this _____ day of August, 1951

My Commission expires July 18, 1955

Oliver Ann Fair