

**STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION**

FORM CP-1
Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-185-23333-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: Mull Drilling (owner/company name) KCC LICENSE # 5144 *6/10/06*
(operator's)

ADDRESS: P.O. Box 2758 CITY: Wichita
STATE: Kansas ZIP CODE: 67201-2758 CONTACT PHONE: 316-264-6366

LEASE: McIlvain WELL#: 1-11 Section 11 Township 21s Range 13w
S/2 SW NW NE SPOT LOCATION/QQQQ COUNTY: Stafford

~~1780~~ 1240 FEET (in exact footage) FROM ^{North} ~~South~~ LINE OF SECTION (NOT Lease Line)
~~1260~~ 2310 FEET (in exact footage) FROM ^{East} ~~West~~ LINE OF SECTION (NOT Lease Line)

KCC - SKA - 12-21-05 - Per RADM 94 Scout Card

Check One: Oil Well Gas Well D&A SWD/ENHR WELL Docket # _____
CONDUCTOR CASING SIZE None SET AT NA CEMENTED WITH NA SACKS _____
SURFACE CASING SIZE 8-5/8" SET AT 271' KB CEMENTED WITH 275 SACKS _____
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS _____

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 1876 G.L. 1885 K.B. T.D. 3710 PBDT _____ Anhydrite Depth 720-746
(Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING:
Plugged well on 12/08/05 in this manner: Heavy mud in hole and between all plugs. Used 175 sx of 60/40 Poz, 6% Gel. Bottom plug at 3400' - 40 sx, 2nd plug at 760' - 50 sx, 3rd plug at 310' - 50 sx, top plug at 60' - 20 sx, Rathole - 15 sx, no mousehole. Job completed at 8:00 pm on 12/09/05. Allied Cementing ticket #24728. Plugging orders from Ken Jeblick on 12/08/05. Sterling reported plugging to KCC on 12/09/05.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Name: Lonnie Saloga Phone#: (620) 672-9508
Address: P.O. Box 1006 City: Pratt State: Kansas
PLUGGING CONTRACTOR : Sterling Drilling Company KCC LICENSE #: 5142 *6/10/06*
(company name) (contractor's)
Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged 12-8-2005
PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator Agent

DATE: 12/09/05 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott
(signature) Gary M. Talbott, Agent for Operator

**RECEIVED
DEC 13 2005
KCC WICHITA**

KCC WICHITA

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Mcllvain 1-11

LOCATION: S/2 SW NW NE
API: 15-185-23333-0000

Section 11 T 21s R 13w
Stafford County, Kansas

OWNER: Mull Drilling
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 29-Nov-05
COMPLETED: 09-Dec-05

TOTAL DEPTH: DRILLER 3710 FEET
LOGGER 3711 FEET

Ground Elevation: 1876
KB Elevation: 1885

LOG

| | | | |
|--------|-----------|-------------------------------|-------------------------|
| 0 - | 2 FEET | Top Soil | From Water Well Driller |
| 2 - | 18 FEET | Clay | |
| 18 - | 25 FEET | Fine Sand | |
| 25 - | 50 FEET | Clay | |
| 50 - | 75 FEET | Fine Sand | |
| 75 - | 100 FEET | Sand and Gravel | |
| 100 - | 720 FEET | Redbeds | |
| 720 - | 746 FEET | Anhydrite (Driller's) | |
| 746 - | 1550 FEET | Shales and Salt | |
| 1550 - | 3650 FEET | Limestone, Shale and Dolomite | |
| 3650 - | 3710 FEET | Arbuckle | |

CASING RECORDS

Surface Casing-8-5/8"

Spud at 3:00 pm on 11/29/05. Drilled 12-1/4" hole to 275'. Ran 7 joints of new, 20#, 8-5/8" surface casing, tallied 261.59', set at 271' KB. Cemented with 275 sx 70/30 Poz, 2% Gel, 3% CC. Cement did circulate. Plug down at 10:00 pm on 11/29/05. Allied Cementing ticket # 22614. Welder strapped bottom 3 joints together and welded collars on remaining joints.

Production Casing

Plugged well on 12/08/05 in this manner: Heavy mud in hole and between all plugs. Used 175 sx of 60/40 Poz, 6% Gel. Bottom plug at 3400' - 40 sx, 2nd plug at 760' - 50 sx, 3rd plug at 310' - 50 sx, top plug at 60' - 20 sx, Rathole - 15 sx, no mousehole. Job completed at 8:00 pm on 12/09/05. Allied Cementing ticket #24728. Plugging orders from Ken Jeblick on 12/08/05. Sterling reported plugging to KCC on 12/09/05.

DEVIATION SURVEYS

1/4 degree(s) at 275 feet
1-1/4 degree(s) at 3360 feet
3/4 degree(s) at 3710 feet

RECEIVED
DEC 13 2005
KCC WICHITA