

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
211 NORTH BROADWAY  
WICHITA, KANSAS

15-065-00852-00-00

WELL PLUGGING APPLICATION FORM  
File One Copy

Lease Owner Osage Oil & Gas Co. Address 531 Petroleum Building, Wichita, Kansas  
(Applicant)

Lease (Farm Name) WORCESTER Well No. 1

Well Location SW/4 SE/4 NE/4 Sec. 23 Twp. 7S Rge. 22 (E) - (W) W

County Graham Field Name (if any) \_\_\_\_\_

Total Depth 3800 Oil Gas Dry Hole Dry Hole

Was well log filed with application? Yes If not, explain: \_\_\_\_\_

Date and hour plugging is desired to begin March 23, 1956 6:00 a.m.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well for owner \_\_\_\_\_

S. J. Fickel Address Plainville, Kansas

Plugging Contractor Eldon Petty

Plugging Contractor's License No. \_\_\_\_\_

Address Box 326, Hays, Kansas

Invoice covering assessment for plugging this well should be sent to \_\_\_\_\_

Osage Oil & Gas Co. Address 531 Petroleum Building, Wichita, Ks.

and payment will be guaranteed by applicant.

HEATHMAN-SEELIGSON DRILLING CO.

By: [Signature]  
Applicant or Acting Agent

Date March 27, 1956

**PLUGGING**  
FILE SEC 23 T 7 R 22W  
BOOK PAGE 48 LINE 14

3-29-56

15-065-00892-00-00

DRILLERS' LOG

NAME: WORCESTER #1 DATE SPUDDED: 3-14-56  
 LOCATION: SW/4 SE/4 NE/4 Sec.23-7S-22W ROTARY COMPLETED: 3-23-56  
 Graham County, Kansas  
 OPERATOR: Osage Oil & Gas Co. ELEVATION: 2214 GR  
 2216 DF  
 2219 KB  
 CONTRACTOR: Heathman-Seeligson Drilling Co. ROTARY TOTAL DEPTH: 3800'  
 SURFACE CASING: Ran 5 jts. of 8-5/8" used csg. cemented at 158.52' w/150 sacks cement, 2 Calcium Chloride. Cement Circulated.  
 OIL STRING: None run - Dry and abandoned 3-23-56

DRILL STEM TESTS

DST #1, 3520-47, open 1 hr. strong blow, rec. 330' muddy saltwater. IFP-50#, FFP-330# BHP-1200#.

GEOLOGICAL TOPS (KB)

Heebner	3424 (-1205)
Toronto	3443 (-1224)
Lansing	3457 (-1238)
B. Kansas City	3656 (-1437) >199'
Conglomerate	3743 (-1524)
Arbuckle	3799 (-1580)

L O G

(Figures indicate bottom of formation)

Shale & Sand	0 - 745
Sand	900
Shale & Sand	1150
Shale, Shells & Red Bed	1250
Shale & Sand	1520
Shale & Red Bed	1795
Shale & Shells	1797
Anhydrite	1835
Shale & Shells	2060
Anhydrite	2105
Shale & Shells	2335
Shale & Lime	3465
Lime	3665
Shale & Lime	3730
Conglomerate	3800

The undersigned, H. D. Shreve, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Report.

HEATHMAN-SEELIGSON DRILLING CO.


By: *H. D. Shreve*

Subscribed and sworn to before me the 27th day of March, 1956

*D. Marjorie Mott*  
Notary Public

My commission expires: June 28, 1956

3-29-56





STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
211 NORTH BROADWAY  
WICHITA, KANSAS

March 26, 1956

15-065-00852-00-00

Well No.	1
Lease	Worcester
Description	SW SW NE 23-7-22N
County	Graham
File No.	18-1h

Osage Oil & Gas Company  
531 Petroleum Building  
Wichita, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

By S. S. Greider  
S. S. Greider  
WELL PLUGGING SUPERVISOR

cc:  
District Plugging Supervisor