

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC
BEM
12-14-05
RSDMS
Per CP 1

Lease Operator: Southern Star Central Gas Pipeline
Address: 4700 Ky. Hwy. 56 West P.O. Box 20010 Owensboro, Ky. 42304
Phone: (270) 852-4490 Operator License #: 33097

Type of Well: ENHR WSW Docket #: E-11165
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 9/30/2005 (Date)

by: Tom Welsh (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Peru Ss. Depth to Top: 704' Bottom: 725' T.D. 725'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 003-22912-00-00

Lease Name: North Koch (South Welda)

Well Number: WSW # 1

Spot Location (QQQQ): NW / SW - SE - NE
3080' Feet from North / South Section Line

1100' Feet from East / West Section Line

Sec. 16 Twp. 22 S. R. 19 East West

County: Anderson

Date Well Completed: 7/1/1998

Plugging Commenced: 10/17/2005

Plugging Completed: 10/18/2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Peru Ss.	oil	0	20	8 5/8"	20	
		0	672'	4.5"	80 sks.	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run 1" to 675' in 4.5". Could not get well to circulate. Well taking water. Pumped 50 sks. Type A cement for bottom plug.

Ran 1" to 485' in 4.5" and tagged cement. Pumped cement to surface, pulled pipe, topped well off with 40 sks. Type A cement.

Casing cut 4' below surfaced and capped

Name of Plugging Contractor: Splane Pulling & Roustabout Service License #: 6372

Address: P.O. Box 386 Chanute, Kansas 66720

Name of Party Responsible for Plugging Fees: Southern Star Central Gas Pipeline

State of Kentucky County, Daviess, ss.

D. Mark Rouse (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) D. Mark Rouse

(Address) SSCGP P.O. Box 20010

SUBSCRIBED and SWORN TO before me this 10th day of December, 2005

Elizabeth A. Morris My Commission Expires: 7/29/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 12 2005
KCC WICHITA

BEM