

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

DEC 09 2005

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Form CP-4
December 2003

KCC WICHITA

Lease Operator: RJ Patrick Operating, LLC

Address: PO Box 1157 Liberal KS 67905

Phone: (620) 624-8483 Operator License #: 33578

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: 11-28-05 (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-081-20474-00-00

Lease Name: Daniels

Well Number: 6-25

Spot Location (QQQQ): W2 NE - NW

4620 Feet from North / South Section Line

3400 Feet from East / West Section Line

Sec. 25 Twp. 29 S. R. 33 East West

County: Haskell

Date Well Completed: 11-18-87 (SPUD)

Plugging Commenced: 11-29-05

Plugging Completed: 12-1-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				16	40	-
				8 ⁵ / ₈	1646	-
				4 ¹ / ₂	4660	2511

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 100 lb. hulls to 25 sx cmt. to plug open hole from 4660 to 4300. Shot & pull 4¹/₂ to 1650. Mixed 50 sx plug 1650 to 1500, 40 sx 650 to 530 10 sx 40 to 0. Used mud between all plugs. Capped 8⁵/₈ 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151

Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: R. J. Patrick Operating, LLC

State of KS County, Seward, ss.

R. J. Patrick (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) RJ Patrick

(Address) P.O. Box 1157 Liberal, KS 67905-1157

SUBSCRIBED and SWORN TO before me this 8th day of December, 2005

Jayn Berry My Commission Expires: 04-04-08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



Berry