

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20677-00-00
Spot: N2S2SE Sec/Twnshp/Rge: 36-8S-29W
990 feet from S Section Line, 1320 feet from E Section Line
Lease Name: HOXIE WATERFLOOD TRACT Well #: 2-3
County: SHERIDAN Total Vertical Depth: 3699 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3698	0	150 SX CMT
SURF	8.625	281	0	190 SX CMT

#120²²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/09/2005 10:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN OL, INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 235 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/09/2005 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 281' w/190 sxs cement.
4 1/2" production casing set at 3698' w/150 sxs cement.
PBTD 3695'. TD 3699'. DV Tool at 2393' w/500 sxs.
Production casing in poor condition.
Ran tubing to 2770' - pumped 75 sxs cement with 300# hulls.
Pulled tubing to 1820' - pumped 50 sxs cement with 150# hulls.
Pulled tubing to 910' - pumped 60 sxs cement with 50# hulls - cement to surface.
Pulled tubing to surface. Connected to 4 1/2" production casing - pumped 20 sxs cement.
Max. P.S.I. 300#. S.I.P. 0#.
Connected to 8 5/8" surface casing - pumped 10 sxs cement.
Max. P.S.I. 300#. S.I.P. 0#
Welded braden head ruptured.

Perfs:

Top	Bot	Thru	Comments
3611	3618		

RECEIVED
DEC 19 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #21798.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

INVOICED
DATE 12-20-05
INV. NO. 3006060889

DEC 12 2005

JOHN O. FARMER, INC.

P.O. BOX 352

RUSSELL, KS 67665

#2 "TR" HOXIE WATERFLOOD W3

36-8-29W


C N/2 S/2 SE

CONTR COMPANY TOOLS

CTY SHERIDAN

GEOL

FIELD HOXIE



ELV 2781 KB SPD 4/30/83

CARD ISSUED 7/21/83

IP P 8 BOPD

API 15-179-20,677

WAB (HOW) 3611-3618

SMP	Tops	Depth/Datum
ANH	2394+ 387
B/ ANH	2431+ 350
HOW	3540- 759
RTD	3699- 918
NO LOG		

8 5/8 " 281/190SX; 4 1/2 " 3698/150SX

DST (1) 3520-3550 (HOW) / 45-45-45-45, REC 150' DM, 250' MW, SIP 339-239#, FP 42-197 / 197-218#

DST (2) 3589-3620 (HOW) / 30-30, REC 30' GSY SOCM, ISIP 280# - NO FSIP, FP 31-42# / NO FFP

MICT - CO, PF (HOW) 3611-18 W/4 SPF, AC 500G, SWB LD, SO, T&R, POP, P 8 BOPD, 6/17/83

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS