

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24433-00-00
Spot: SENW Sec/Twnshp/Rge: 21-14S-19W
3300 feet from S Section Line, 3300 feet from E Section Line
Lease Name: DON KRAUS SOUTH Well #: 6
County: ELLIS Total Vertical Depth: 3766 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3725		
PROD	5.5	3764	0	185 SX CMT
SURF	8.625	210	0	135 SX CMT

\$122⁴⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/08/2005 3:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered 300 sxs cement and 600# hulls.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 12/08/2005 4:30 PM

Witness Type: COMPLETE (100%)
KCC Agent: ROGER MOSES

Actual Plugging Report:

Port collar at 1430' w/375 sxs.
Tied to 5 1/2" casing - squeezed 220 sxs cement with 600# hulls.
Max. P.S.I. 800#. S.I.P. 800#.
Tied to 8 5/8" annulus - squeezed 10 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.
Total of 230 sxs 60/40 pozmix - 10% gel and 600# hulls.

RECEIVED
DEC 22 2005
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
3671	3692		
3623	3639		
3590	3593		
3460	3464		

Remarks: AMERICAN TANK-WATER.

Plugged through: CSG

District: 04

Signed Roger L Moses
(TECHNICIAN)

HO

INVOICED

DATE 12-22-05

INV. NO 2006060895

DEC 16 2005

replacement card

MICHAEL D. WEILERT OIL COMPANY
HAYS, KS 67601


21-14 -19W
C SE NW

#6 KRAUS

site: 5-3/4 S & 1/2 W OF YOCEMENTO, KS
contr: HELBERG OIL COMPANY
geol: J. B. GREEN

city: ELLIS
field: KRAUS

API 15-051-24433



fr date 09/25/86 spd date 10/08/86 drig comp 10/16/86 card issued 02/05/87 last revised 03/02/88

ELV: 2148 KB LOG

tops.....depth/datum

*ANH1417 +731

*B/ANH.....1457 +691

TOP.....3121 -973

HEEB.....3388 -1240

TOR.....3408 -1260

LANS.....3434 -1286

BKC.....3683 -1535

ARB DOL SD.....3761 -1613

RTD.....3766 -1618

*SAMPLE TOP

IP status:

OIL, P 10 BO & 30 BWPD, SHAW 3408-3410 , LKC
3460-3692 OA , ARB OH 3764-3766

CSG: 8-5/8" 210 / 135 SX, 5-1/2" 3764 / 185 SX, MULTI
STAGE COLLAR AT 1430 / 375 SX

NO CORES

DST (1) 3752-3766 (ARB), / TIMES NA, 60' GIP, REC
330' MO ISIP 697# FSIP 689# IFP 58# -92# FFP 117#
-134#

MICT - CO, (ARB OH), GSO, NAT, PF (LANS L) 3692-
3671, W / 1 SPF, AC 500 GAL, PF (LANS K) 3634-3638 &
(LANS J) 3620-3626, W / 2 SPF, AC 2000 GAL, PF (LANS
I) 3590-3593, W / 2 SPF, GSO, NAT, PF (LANS C) 3460-
3464, W / 2 SPF, AC 1250 GAL, GSO, PF (TOR) 3408-
3410, W / 2 SPF, AC 250 GAL, GSO, T&R, POP, P 10
BO & 30 BWPD (GR 35), 11/13/86, COMMINGLED

INFO RELEASED: 3/2/88 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS