

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20484-00-00  
Spot: SENE5W Sec/Twnshp/Rge: 18-11S-22W  
1650 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: HARGER A Well #: 1  
County: TREGO Total Vertical Depth: 3915 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: BOX 783188 8100 E 22ND ST. N. #700  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3913	0	w/200 sxs cmt
SURF	8.625	170	0	w/130 sxs cmt

#127<sup>24</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/19/2005 10:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: PETE FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (785) 623-1506

Proposed Plugging Method: Ordered out 280 sxs 60/40 pozmix - 10% gel - 800# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/19/2005 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

Perforated casing at 1700' and 850'.  
TIH with tubing to 3710' - mixed and pumped 50 sxs cement with 100# hulls.  
Pulled up to 2710' - spotted 50 sxs cement with 200# hulls.  
Pulled up to 1675' - spotted 50 sxs cement with 200# hulls.  
Pulled up to 665' - circulated cement with 30 sxs cement with 100# hulls.  
POOH. Swaged onto 4 1/2" and topped with 10 sxs cement.  
Max. P.S.I. 400#. S.I.P. 250#.  
Hooked up to the annulus and pumped 60 sxs cement with 150# hulls.  
Max. P.S.I. 300#. S.I.P. 150#.

RECEIVED  
DEC 27 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

HO

Signed Jay Pfeifer (TECHNICIAN)

INVOICED  
DATE 12.27.05  
INV. NO. 20060609/4.

DEC 21 2005

A. SCOTT RITCHIE  
 SUITE 950, 125 N. MARKET #1 HARGER "A" 18-11-22W  
 WICHITA, KS. 67202 SE NE SW  
 CONTR MURFIN DRG. CO. CTY TREGO

GEOL \_\_\_\_\_ FIELD HLXSON

E 2204 KB CM 7/14/78 CARD ISSUED 10/26/78 IP P 19 BOPD  
 LANS 3540-44

+	+
+	+
+	+
+	+

API 15-195-20,484

LOG TOPS	DEPTH	DATUM
ANH	1663	+ 541
B ANH	1706	+ 498
TOP	3217	-1013
HEEB	3429	-1225
TOR	3451	-1247
LANS	3467	-1263
B KC	3695	-1491
MARM	3788	-1584
ARB	3904	-1700
LTD	3915	-1711
RTD	3915	-1711

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

8-5/8" 170/130 SX, 4 1/2" 3913/200 SX  
 DST (1) 3393-3465/30-30-30-30, 62'  
 HOCM, SIP 373-273#, FP 74-74#,  
 74-74#  
 DST (2) 3461-3488/30-30-60-45, 25'  
 FO, 840' SG & OCMW, SIP 902-878#,  
 FP 49-248#, 248-422#  
 DST (3) 3493-3515/30-30-60-45, 640'  
 VSO & GCW, SIP 735-735#, FP 49-  
 124#, 174-323#  
 DST (4) 3515-3548/30-30-30-30, 72'  
 HOCM, 310' CGCO, SIP 620-597#,  
 FP 72-96#, 120-168#  
 DST (5) 3589-3658/30-30-30-30, 62' M,  
 SIP 1208-1185#, FP 49-49#, 74-74#  
 DST (6) 3656-3686/30-30-30-30, 10' M  
 W/SP O, ALL PRESS 24#

MICT - CO, PF (MRM) 1/3817, 1/3806, 1/3799, SWB DRY, SO, SD/  
 ON, FU 125' O, AC 2100, REC PT LD, SWB AVG .87 BFPH, 65% O/  
 4 HRS, PF 3816-19, 3805-3808, 3798-3801, 1/3634, 1/3611, BP @  
 3740, SWB DRY, AC 1200, SWB AVG 5.86 BFPH, 10% O, DECR TO TR  
 O LAST 3 HRS, SD/ON, FU 1500' W, SQZ 3634 & 3611, PF 3/3550-  
 51, BP @ 3590, UNABLE TO PUMP WTR INTO PERFS, PULL PLUG & PF  
 1/3540 & 1/3523, BP @ 3544, SWB DRY, NFN/2 HRS, AC 1400, SWB  
 PT LD, SWB 25 BWPH + SSO, SQZ 3523 & 3540, W/100 SX, PULL  
 PLUG & PF 16/3540-44, BP @ 3547, SI/30", FU 100' O + 20' W,  
 SD/ON, FU 210' FL, 80% O, AC 250, REC LD, SWB AVG 2.39 BFPH,  
 TR WTR LAST 2 HRS, SD/ON, FU 950' O, N/W, PULL PLUG @ 3547,  
 T&R, POP

INDEXED