

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00876-00-00
Spot: NENWSE Sec/Twnshp/Rge: 36-12S-22W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: OGALLAH UNIT Well #: 16-2
County: TREGO Total Vertical Depth: 3985 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3978	0	150 SX CMT
SURF	8.625	248	0	125 SX CMT

#129⁵¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2005 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-5100

Proposed
Plugging
Method:

Ordered 375 sxs cement and 800# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/14/2005 11:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

November 1972 - squeezed at 1410' w/100 sxs cement.
November 2003 - squeezed at 2500' w/250 sxs cement.
November 2003 - squeezed at 2500' w/200 sxs cement.
Ran tubing to 2000' - circulated with 145 sxs cement with 400# hulls.
Pulled all tubing - squeezed 5 1/2" casing with 35 sxs cement and 100# hulls.
Max. P.S.I. 800#. S.I.P. 800#.
Tied to 8 5/8" x 5 1/2" annulus - pressured to 300# P.S.I. - took no cement.
Total of 180 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3967	3976		

RECEIVED
DEC 27 2005
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS MONROE #2. ALLIED CEMENTING COMPANY. SHANE'S TANK SERVICE-WATER.

Plugged through: TBG

District: 04

Signed Roger A. Moses
(TECHNICIAN)

INVOICED

DATE 12.27.05

INV. NO. 2006060917

Form CP-2/3

DEC 22 2005

36-12-22W
NE NW SE

H G KAISER #2 MONROE

Contr. M B ARMER TREGO County


E 2315 RBComm. Comp. 6-19-53 IP 261 BOPD
PHY POT

Tops	Depth	Datum
Arh	1714	7601
ARB	3962	-1647
TD	3984	-1669

Casing
8" 248
5" 3978

2 BOPH: ACID 500: 10
BOPH/3 HRS:

OGALLAH POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

36-12-22W
NE NW SE