

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00805-00-02
Spot: SESESW Sec/Twnshp/Rge: 6-9S-16W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: KERN RYAN Well #: 1
County: ROOKS Total Vertical Depth: 3390 feet

Operator License No.: 33315
Op Name: MAR-LOU OIL CO., LLC
Address: PO BOX 218
WILSON, KS 67490

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3390	0	175 SX CEMENT
SURF	8.625	234	0	140 SX CEMENT

18
#110

Well Type: EOR UIC Docket No: E22292.1 Date/Time to Plug: 10/03/2005 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: LARRY WALLERT Company: WALLEY'S SERVICE Phone: (785) 735-4895

Proposed
Plugging
Method:

Ordered out 270 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/03/2005 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Tubing parted at 1280'.
TIH with tubing to 1280'. Hit top of fish - pulled up to 1260'.
Mixed and pumped 100 sxs cement. POOH.
Swaged onto 4 1/2" and pumped 150 sxs cement with 500# hulls.
SIFN.
Tagged top of cement at 247'.
Ok'd to fill with dry cement.
12/16/2005 - Filled with 20 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3087	3352		

RECEIVED
DEC 27 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 12.27.05

INV. NO 2006060914

Form CP-2/3

DEC 21 2005

WOODWARD & CO #1 KERN 6-8-64
 SE SE SW
 Contr. BERGMAN DRILG ROOKS
 E1968 RB Comm. Comp. 5-12-64 D & A

Tops	Depth	Datum
HOW	2823	-855
TOP	2852	-884
HEEB	3070	-1102
TOR	3090	-1122
LANS	3111	-1143
ARB	3428	-1460
TD	3438	-1470

Casing
 8" - 240'
 DST 5880-30/2 MR. 250' 00" TW
 M. PMP 5880/25" - 3000/25"
 DST 5880-3425/1 MR. 51' Y. 8"
 960/30" - 885/30"

LEE CORNELL, GEO.

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

13310101
 13310101
 13310101