

3 022969

15-207.19639-00W

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050019-061  
NE,SW,NE 1/4 Sec/Twp/Rge S.28-T.25S.-R.17E.  
3666 feet from south section line  
1457 feet from east section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 101 100  
Operator: STATE OF KANSAS Fee Fund  
Name & \_\_\_\_\_  
Address \_\_\_\_\_  
AB oil well X Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_

Lease/Well# BENNETT B. NO.15  
County WOODSON  
Well Total Depth 750' feet  
Production Pipe: \_\_\_\_\_ Size Feet \_\_\_\_\_  
Surface Casing: 12" Size Feet 10'  
D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: KW OIL WELL SERVICE Lic. # 3097 8933

Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 9:00A.M. Day: \_\_\_\_\_ 1 Month: 12 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WAS A BURRIED WELL NOT VISIBLE AT SURFACE. 10" of 12" PIPE

WAS INSTALLED TO BRING THE WELL TO SURFACE. THE PLUGGING PROPOSAL

WAS TO DRILL OUT THE WELL AND TO CIRCULATE AS MUCH OF THE WELL AS

POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All \_\_\_\_\_ Part X \_\_\_\_\_  
TECHNICIAN  
None \_\_\_\_\_

Operations Completed: Hour: 12:00P.M. Day: \_\_\_\_\_ 1 Month: 12 2005

Actual Plugging Report: THE WELL WAS DRILLED OUT TO 180'. AT THAT DEPTH

IRON WAS ENCOUNTERED IN THE WELL. 1" PIPE WAS RAN INTO THE WELL TO 175'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE

SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT

WAS FILLED FROM SURFACE. 39 SACKS OF CEMENT WERE PUMPED INTO THIS

WELL.

Remarks: ( GPS SESSION PT. NO.15.) (THIS WELL WAS NOT NUMBERED ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED  
DEC 19 2005  
KCC WICHITA

Signed:

Clayton P. Titel  
TECHNICIAN

*[Handwritten signature]*