

3 022967

15-207-19658 000

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050019-060
NE,SW,NE 1/4 Sec/Twp/Rge S.28-T.25S.-R.17E.
3507 feet from south section line
1615 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 106-400
Operator: STATE OF KANSAS Fee Fund
Name & _____
Address _____
AB oil well X Gas Well _____ SWD Well/ Input Well _____

Lease/Well# BENNETT B. NO.14
County WOODSON
Well Total Depth 750' feet
Production Pipe: _____ Size Feet _____
Surface Casing: 12" Size Feet 20'
D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KW OIL WELL SERVICE Lic. # 3097 8933
Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 9:00A.M. Day: _____ Month: 11 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WAS A BURRIED WELL NOT VISIBLE AT SURFACE. 20" OF 12" WAS INSTALLED TO BRING THE WELL TO SURFACE.THE PLUGGING PROPOSAL WAS TO DRILL OUT THE WELL AND CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL
TECHNICIAN
Plugging attended by Agent: All _____ Part X None _____

Operations Completed: Hour: 12:00P.M. Day: _____ Month: 11 2005

Actual Plugging Report: THE WELL WAS DRILLED OUT TO 450'. AT THAT DEPTH IRON WAS ENCOUNTERED IN THE WELL. 1" PIPE WAS RAN INTO THE WELL TO 450'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 12" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 201 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.14.) (THIS WELL WAS NOT NUMBERED ON THE LEASE MAP)
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED
DEC 19 2005
KCC WICHITA

Signed: Clayton P. Titel
TECHNICIAN

[Handwritten signature]