

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25448-00-00  
Spot: N2NESESE Sec/Twnshp/Rge: 10-11S-20W  
1190 feet from S Section Line, 330 feet from E Section Line  
Lease Name: HAZEL Well #: 10-1  
County: ELLIS Total Vertical Depth: 3702 feet

Operator License No.: 33335  
Op Name: IA OPERATING, INC.  
Address: 900 N TYLER ROAD #14  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1411		

# 120 32

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2005 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: ANDY DINKEL Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 205 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE  
Date/Time Plugging Completed: 12/22/2005 1:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3599' w/25 sxs.  
2nd. Plug at 1465' w/50 sxs.  
3rd. Plug at 725' w/95 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.


Perfs:

RECEIVED  
DEC 27 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed   
(TECHNICIAN)

INVOICED

DATE 12.27.05  
INV. NO. 2006060913

Form CP-2/3

DEC 23 2005