

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-127-20278-00-01
Spot: NENE Sec/Twnshp/Rge: 14-15S-5E
4736 feet from S Section Line, 745 feet from E Section Line
Lease Name: KENDALL Well #: 1
County: MORRIS Total Vertical Depth: 2182 feet

Operator License No.: 30483
Op Name: KREMEIER, LES DBA KREMEIER PROD
Address: 3183 US HIGHWAY 56
HERINGTON, KS 67449

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2173		
SURF	8.625	250		

A 70⁹²

Well Type: EOR UIC Docket No: E27881.1 Date/Time to Plug: 11/15/2005 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: LES KREMEIER Company: KREMEIER PROD. AND OPER. CO. Phone: (785) 258-2544

Proposed
Plugging
Method:

Sand to 50' above bridge plug and cap with 4 sxs cmt. Pull tubing to 330' and circ cmt to surf.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL
Date/Time Plugging Completed: 11/15/2005 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

11/15/2005 -- CIBP @ 2150'. Sanded to 2053' and pumped 15 sacks of cement at 2053'. Pulled tubing to 330' and circulated 185 sacks of cement to surface. Plug dropped to approximately 70'.
11/21/2005 -- Operator brought 30 sacks of cement and mixed with water from water truck to bring plug to surface.
60/40 posmix with 4% gel
United Cementing #6652

Perfs:

RECEIVED
KCC DISTRICT #2
DEC 14 2005
WICHITA, KS

RECEIVED
DEC 23 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Greg Eves

(TECHNICIAN)

INVOICED

DATE 12-23-05

INV. NO. 2006060905