

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-19030-00-01  
Spot: SWSW Sec/Twnshp/Rge: 22-28S-7W  
660 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: ALAMEDA Well #: 2-2  
County: KINGMAN Total Vertical Depth: 4457 feet

Operator License No.: 3880  
Op Name: KC RESOURCES, INC. DBA CRYSTAL R  
Address: P. O. BOX 6749  
SNOWMASS VILLAGE, CO 81615

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4377		
PROD	5.5	4445		140 SX
SURF	8.625	286		200 SX

*\$144<sup>85</sup>*

Well Type: EOR UIC Docket No: E13079.4 Date/Time to Plug: 11/18/2005 1:00 PM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: JOE WISHNUCK Company: KC RESOURCES, INC. DBA CRYST Phone: (405) 642-1516

Proposed Plugging Method:

See actual report.

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/18/2005 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Ran 118 joint of tubing to 3683'. Spotted 80 sacks of cement (tag 3550'). Pulled tubing to perforations at 1150' and spotted 35 sacks of cement. Pulled tubing to perforations at 750' and spotted 35 sacks of cement. Pulled tubing to perforations at 350' and circulated cement to surface with 119 sacks of cement.

60/40 posmix with 4% gel and 200 lbs of cotton hulls

United #6257  
Log Tech #16000

Perfs:

Top	Bot	Thru	Comments
4376	4380		
4024	4029		
4019	4020		
3715	3724		

RECEIVED  
KCC DISTRICT #2  
DEC 14 2005  
WICHITA, KS


RECEIVED  
DEC 23 2005  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

**INVOICED**

DATE 12-23-05  
INV. NO. 2006060904