

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21353-00-00  
Spot: N2NENWSE Sec/Twnshp/Rge: 1-19S-8W  
2410 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: BURDETTE A Well #: 3  
County: RICE Total Vertical Depth: 3350 feet

Operator License No.: 8917  
Op Name: GUSTUS, DEAN DBA JD PRODUCTION  
Address: 701 MAIN  
GENESEO, KS 67444

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3348	2152	150 SX CMT
SURF	8.625	275	0	200 SX CMT

#108 88

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/02/2005 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE  
Date/Time Plugging Completed: 12/02/2005 4:00 PM KCC Agent: VIRGIL CLOTHIER

**Actual Plugging Report:**

Sanded perforations to 2850' and capped with 5 sacks of cement. Cut off casing at 2150'. Pulled casing to 1075' and pumped 35 sacks of cement with 200 lbs of cotton hulls. Pulled casing to 725' and pumped 35 sacks of cement. Pulled casing to 325' and circulated cement to surface.

60/40 posmix with 4% gel

United Cement #6724

**Perfs:**

Top	Bot	Thru	Comments
2901	2904		

**RECEIVED  
KCC DISTRICT #2  
DEC 14 2005  
WICHITA, KS**

**RECEIVED  
DEC 23 2005  
KCC WICHITA**

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

**INVOICED**  
DATE 12.23.05  
INV. NO 2006060902