

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20466-00-00
Spot: W2SWSW Sec/Twnshp/Rge: 6-20S-10W
636 feet from S Section Line, 5036 feet from E Section Line
Lease Name: SCHARTZ LOUIS Well #: 1
County: RICE Total Vertical Depth: 3380 feet

Operator License No.: 33315
Op Name: MAR-LOU OIL CO., LLC
Address: PO BOX 218
WILSON, KS 67490

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|------------|
| PROD | 6 | 3380 | | 175 SX CMT |
| SURF | 8.625 | 250 | | 200 SX CMT |

#10985

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/09/2005 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 12/09/2005 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3000' and capped with 5 sacks of cement. Perforated at 1300', 900', and 300'. Ran tubing to 1300' and pumped 35 sacks of cement. Pulled tubing to 900' and pumped 35 sacks of cement. Pulled tubing to 300' and circulated cement to surface.

60/40 posmix with 4% gel

Allied Cement #22677

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|---|
| 3058 | 3061 | | RECEIVED KCC DISTRICT #2 DEC 14 2005 WICHITA, KS |
| | | | RECEIVED DEC 23 2005 |

Remarks:

Plugged through: TBG

KCC WICHITA

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 12-23-05
INV. NO 2006060907