

3 022917

15-207-19623-00-00

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050019-011
SE,SW,NE 1/4 Sec/Twp/Rge S28-T.25S.-R.17E.
3174 feet from south section line
1933 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS Fee Fund

Lease/Well# BENNETT B NO. 07

County WOODSON

Name & _____

Well Total Depth 750' feet

Address _____

Production Pipe: 2" Size Feet 750'

Surface Casing: 8" Size Feet 20'

AB oil well X Gas Well _____ SWD Well/ Input Well _____

D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W OIL WELL SERVICE

Lic. # 3097

Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 1:00P.M. Day: 12 Month: 10 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT

HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE 2"

CASING.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____

TECHNICIAN

None X

Operations Completed: Hour: 5:30P.M. Day: 12 Month: 10 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 700'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE

2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO

THE 2" AND 8" ANNULUS TO 500'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL

CEMENT CIRCULATED FROM THE SURFACE CASIN AT SURFACE. THE 1" PIPE WAS

REMOVED. DISPLACEMENT WAS FILLED FROM SURFCE.238 SACKS OF CEMENT

WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.3) (THIS WAS WELL NO.7 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED

NOV 04 2005

KCCWICHITA

Bm