

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24423-00-00  
Spot: SENENE Sec/Twnshp/Rge: 16-16S-13W  
4290 feet from S Section Line, 330 feet from E Section Line  
Lease Name: DEUTSCH Well #: A-2  
County: BARTON Total Vertical Depth: 3519 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 4514 COLE AVE., STE 740, LB 30  
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3408		
PROD	5.5	3519	0	160 SX CMT
SURF	8.625	401	0	250 SX CMT

# 114 37

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/13/2005 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 245 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/13/2005 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3315' and topped with 5 sxs cement using a dump bailer.  
Cut casing free at 2200'.  
Pulled up to 1700' - mixed and pumped 115 sxs cement with 300# hulls.  
Pulled up to 880' - spotted 40 sxs cement with 100# hulls.  
Pulled up to 450' - spotted 30 sxs cement with 100# hulls.  
Pulled up to 200' and circulated cement with 30 sxs cement.  
POOH. Hole full of cement.

Perfs:

Top	Bot	Thru	Comments
3412	3414		
3393	3395		

RECEIVED  
DEC 15 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED

DATE 12-15-05

INV. NO 2006060875

DEC 13 2005

STATE: KANSAS COUNTY: BARTON REISSUE 16-16S-13W  
FIELD: TRAPP SE NE NE  
OPER: HALLWOOD PET 4290 FSL 330 FEL SEC  
WELL: A-2 DEUTSCH ELEV: 1933 KB  
API: 15-009-24423  
SPUD: 06/13/90  
DTD: 3520 LTD: FTD: ARBUCKLE COMP: 07/04/90 1925 GR  
PBTD:

LOC: 1 1/2 MI NE SUSANK, KS

IP: COMP 7/4/90, IPP 4 BO, 214 BWPD PROD ZONE- ARBUCKLE 3393-3414 GROSS  
NO CORES, THREE DSTS

LOG TOPS:

ANHYDRITE	876 1057	LANSING	3153 -1220
TOPEKA	2824 -891	B/ KANSAS CITY	3365 -1432
HEEBNER	3060 -1127	ARBUCKLE	3388 -1455
TD	3520 -1587		

LOG TYPES: CDL, CORL, DILL, DSN, MCL;

CSGS: 8 5/8 @ 392 W/250 SX, 5 1/2 @ 3515 W/160 SX; TBG: 2 7/8 @ 3404; DRLG COMP  
06/16/90

DSTS: DST # 1 (KANSAS CITY) 3152-3200, OP 30 MIN, SI 30 MIN, OP 30 MIN, SI 30 MIN,  
REC: 90 FT MUD, IFP 72, FFP 85, IFP 85, FFP 85, ISIP 477, FSIP 454, IHP 1630, FHP  
1600, DST # 2 (ARBUCKLE) 3360-3392, OP 30 MIN, SI 30 MIN,

(OVER)

COPYRIGHT 1992 PETROLEUM INFORMATION CORPORATION

DATE 04/03/92 CARD #00074-KS

134102