

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23323-00-00
Spot: NENE Sec/Twnshp/Rge: 32-14S-15W
4540 feet from S Section Line, 520 feet from E Section Line
Lease Name: SCHMITT Well #: 1
County: RUSSELL Total Vertical Depth: 3450 feet

Operator License No.: 6627
Op Name: PROSPECT OIL & GAS CORP
Address: PO BOX 837
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	433		

#112¹³

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/09/2005 11:00 AM
Plug Co. License No.: 9431 Plug Co. Name: VONFELDT DRILLING, INC
Proposal Revd. from: DOUG BUDIG Company: VONFELDT DRILLING, INC Phone: (785) 483-6446

Proposed Plugging Method: Order 160 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 12/09/2005 2:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 3450' w/25 sxs.
2nd. Plug at 1000' w/25 sxs.
3rd. Plug at 500' w/75 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

RECEIVED
DEC 15 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 12-15-05

INV. NO 2006060877

DEC 14 2005