

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-20983-00-01
Spot: SESESESE Sec/Twnshp/Rge: 18-35S-12E
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: SOLOMON Well #: 1
County: CHAUTAUQUA Total Vertical Depth: 1105 feet

Operator License No.: 32717
Op Name: MCCOY, RICHARD L.
Address: 350 ROAD 22
PERU, KS 67360

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1105	0	
SURF	7	42	0	

35⁹¹

Well Type: EOR UIC Docket No: E23015.3 Date/Time to Plug: 11/15/2005 5:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S INC.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORES, INC. Phone: (620) 249-2519

Proposed Plugging Method: TO RUN 1" & PUMP CEMENT & GEL FOR BOTTOM & TOP PLUGS.

Plugging Proposal Received By: RON ROWE WitnessType: NONE
Date/Time Plugging Completed: 11/15/2005 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

RAN 1" HYDRIL INSIDE 5.5" CASING TO TD @ 1105', GELLED HOLE & PUMPED 10 SACKS CEMENT FOR BOTTOM PLUG. PULLED 1" TO 750' & PUMPED 5 SACKS CEMENT FOR MIDDLE PLUG. PULLED 1" TO 350' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 1" & TOPPED-OFF WELL. USED TTOAL OF 70 SACKS CEMENT & 2 SACKS GEL.

Perfs:

Top	Bot	Thru	Comments
1052	1089		

RECEIVED
DEC 15 2005
KCC WICHITA

RECEIVED
KCC DISTRICT #3

DEC 8 2005 RR

CHANUTE, KS

Remarks: PLUGGED INJECTION WELL THAT HAD FAILED OPERATORS PRE-TEST MIT.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

INVOICED

DATE 12-15-05

TEL NO 2006060876