

3 022939

15-207-19622-00100

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 2000019-016
SE,NW,NE 1/4 Sec/Twp/Rge S.28-T.25S.-R.17E.
4078 feet from south section line
1490 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: STATE OF KANSAS Fee Fund
Name & _____
Address _____
AB oil well Gas Well _____ SWD Well/ Input Well _____

Lease/Well# BENNETT "B" NO.4
County WOODSON
Well Total Depth 750' feet
Production Pipe: 2" Size Feet 750'
Surface Casing: 8" Size Feet 20'
D & A _____

Other well as hereinafter indicated: _____
Plugging Contractor: K-W OIL WELL SERVICE, INC Lic. # 3097
Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 9:00P.M. Day: _____ 3 Month: 11 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT HAD
BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE
AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part _____
TECHNICIAN
None _____

Operations Completed: Hour: 12:00P.M. Day: _____ 3 Month: 11 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 700'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM
THE 2" CASING AT SURFACE. THE 1" WAS REMOVED. 1" PIPE WAS RAN INTO
THE 2" AND 8" ANNULUS TO 575'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL
CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE
WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 235 SACKS OF
CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.8) (THIS WELL WAS NO.4 ON THE LEASE MAP.)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

RECEIVED
NOV 21 2005
KCC WICHITA

Bm