

6 030687

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21,193-00-00

~~NWNWSE~~ SEC. 21, T 7 S, R 22 ~~W~~ E

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name WORCESTER Well # D 1

Operator: PETROLEUM INC.

County GRAHAM 125.29

Name & Address P.O. Box 1447

Well Total Depth 3855 feet

GREAT BEND, KANSAS

Conductor Pipe: Size _____ feet

67530

Surface Casing: Size 8 5/8 feet 247'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor ROCKHOLD ENGINEERING, INC. License Number 5111

Address Box 698 GREAT BEND KANSAS 67530

Company to plug at: Hour: AM Day: 7 Month: 3 Year: 19 86

Plugging proposal received from DEACON

(company name) ROCKHOLD ENG. (phone) _____

were: 8 5/8 @ 247' w/ 175 sx. 5 1/2 @ 3760' w/ 150 sx. PERF 3492 - 3553

ORDER SAND-COM. CMT. SHOOT & PULL PIPE ORDER 180 sx 60/40 P22 6% GEL

3% CL. 400 sx. GEL 8 5/8 W.P. BJ TITAN CMT. CO. JOHN KEITH WATER TRUCK.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:30AM Day: 7 Month: 3 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND TO 3400' w/ 5 sx. COM CMT ON SANDW/ BAILER

SHOOT & PULL PIPE 800' PULLED.

MIX & Pump DOWN 8 5/8 35 sx. HULLS 32 sx. GEL 100 sx. CMT. MIX. + 15 sx. HULLS 8 sx. GEL

W.P. 80 sx. CMT. MIX. MAX. PSI 600[#] CLOSE IN 200[#] PLUG. COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: 3-24-86 MAR 24 1986
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 25 1986

INV. NO. 13109

Signed Carl Goodrow
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas