

To: **6 070830**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-12
API NUMBER 15- 065-23,556-00-00R
SW SW SW, SEC. 28, T 7 S, R 22 **W/E**
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Hildebrand Well # 1

Operator: Frontier Oil Co
Name &

County Graham **119.28**

Address 125 N. Market #1720
Wichita, Ks. 67202

Well Total Depth 3670 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 224

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger License Number _____

Address 1720 KSB&T Bldg. Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 12 Month: Mar Year: 19 90

Plugging proposal received from Pat Waggoner

(company name) Red Tiger Drilling (phone) _____

were: 8 5/8" 224' s.p. cwc w/150 sks 60/40 poz 6% gel 3% cc. By Allied. K.C. well.

Elv. 2213' Anhy 1862' No circulation problems. Mud condition 45 vis. 9.4 weight. 10

water loss. Proposal 190 sks cement 60/40 poz 6% gel 1 sk f.c. and 8 5/8" plug. Spot with

drill stem heavy mud between all plugs. 25 sks at 1875'; 100 sks w/1 f.c. at 960';

40 sks at 275' 10 sks at 40' w/wiper plug.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 1:30PM Day: 12 Month: March Year: 19 90

ACTUAL PLUGGING REPORT Frontier ordered 190 sks 60/40 poz 6% gel 1 sk f.c. and 8 5/8" plug.
Spotted cement with drill stem with heavy mud between all plugs.

1st plug 25 sks at 1875'. 2nd plug 100 sks w/1 f.c. at 960'. 3rd plug 40 sks at 275'.

4th plug 10 sks w/wiper plug at 40'. 15 sks in rathole cir. Cemented by Allied.

RECEIVED
Remarks: STATE RECORDS **3-20-1990**
(If no additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

Signed Marion J. Schmidt (TECHNICIAN)

Marion J. Schmidt

DATE 3-26-90
INV. NO. 27705
3-12