

3 022956

15-001-02039-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20060001-055

SW,NE,NE 1/4 Sec/Twp/Rge S.24-T.26S.-R.17E.

4440 feet from south section line

753 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSAS Fee Fund

Name & _____

Address _____

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICELic. # 30670Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720Company to plug at: Hour: 8:00A.M. Day: 16 Month: 11 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2 7" CASING TO APPROXIMATELY 850'THAT HAD BEEN CEMENTED IN FROM AT T.D. ONLY. THE 2" CASING WAS PARTEDAT 300" AND THE TOP 300' OF 2" CASING REMOVED. THE PLUGGING PROPOSALWAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.Plugging Proposal Received by: CLAYTON P. TITELPlugging attended by Agent: All _____ Part _____ TECHNICIAN
None ☒Operations Completed: Hour: 1:30P.M. Day: 16 Month: 11 2005Actual Plugging Report: 1" PIPE WAS RAN INTO THE WELL TO 500'. CEMENTWAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACECASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLEDFROM SURFACE. 216 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED

DEC 09 2005

KCC WICHITA

Remarks: (GPS SESSION PT. NO.22) (NO OTHER NO. AVAILABLE.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

Bm