

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25467-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 26-11S-18W
405 feet from N Section Line, 525 feet from W Section Line
Lease Name: PEAVEY Well #: 5
County: ELLIS Total Vertical Depth: 3657 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 W ROAD
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	262		

118⁸⁵

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/09/2005 12:00 AM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: PETE WAGNER Company: BILL BOWMAN OIL COMPANY Phone: (785) 650-9676

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 12/09/2005 5:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

1st. Plug at 3620' w/25 sxs.
2nd. Plug at 1360' w/25 sxs.
3rd. Plug at 760' w/100 sxs.
4th. Plug at 312' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

RECEIVED
DEC 19 2005
KCC WICHITA

Remarks:

Plugged through: DP

District: 04

#10

Signed

Richard Williams
(TECHNICIAN)

INVOICED

DATE 12.20.05

INV. NO. 2006060886

Form CP-2/3

DEC 16 2005