

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Heartland Oil & Gas Corporation  
 Address: 1610 Industrial Park Drive Paola KS 66071  
 Phone: (913) 294-1400 Operator License #: 33233  
 Type of Well: Gas Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 11-16-05 (Date)  
 by: Taylor Herman (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (if needed attach another sheet)  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 131-20191-00-00  
 Lease Name: Bohannon  
 Well Number: 5 - 20  
 Spot Location (QQQQ): \_\_\_\_\_ - \_\_\_\_\_ - SW - NW  
2130 Feet from  North /  South Section Line  
630 Feet from  East /  West Section Line  
 Sec. 20 Twp. 5 S. R. 14  East  West  
 County: Nemaha  
 Date Well Completed: 10-03-04  
 Plugging Commenced: 11-21-05  
 Plugging Completed: 11-21-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	GL	281.7'	8 5/8	281.7'	None
	Production	GL	2686.8'	5 1/2	2686.8'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 2622' and broke circulation with fresh water. Pumped 14.25 bbls of gelled water filling hole from 2622' to 2492'.  
Pulled tubing to 2492', pumped 36 bbls of gelled water and 30 sx of Class A cement with 1 sx of cottonseed hulls.  
Displaced with 8.5 bbls of of gelled water. Had cement from 2492' to 2230'. Filled hole with gel to 332' and circulated cement with 45 sx to surface.

Name of Plugging Contractor: Hurricane Well Service, Inc. License #: 32006  
 Address: PO Box 782228 Wichita KS 67278-2228

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 16 2005


Name of Party Responsible for Plugging Fees: Hurricane Well Service, Inc.  
 State of Kansas County, Sedgwick, ss.

Darrel G. Walters (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) PO Box 782228 Wichita KS 67278-2228



SUBSCRIBED and SWORN TO before me this 15<sup>th</sup> day of December, 2005

[Signature] My Commission Expires: 12-21-2007  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]