

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Mar-Lou Oil Company
Address: Box 218
Phone: (785) 658-2246 Operator License #: 33315
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: _____ (Date)
by: Louis (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 159-20466-00-00
Lease Name: Louis Schartz
Well Number: 1
Spot Location (QQQQ): C - W2 - SW - SW
660 Feet from North / South Section Line
4950 Feet from East / West Section Line
Sec. 6 Twp. 20 S. R. 10 East West
County: Rice
Date Well Completed: _____
Plugging Commenced: 12-06-05
Plugging Completed: 12-09-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	250	
				6	3380	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3000', Baled 5 sacks cement, Had Perf-Tech shoot holes at 1300', 900', 300'. Ran tubing to 1300', pumped 35 sacks cement, pulled to 900', pumped 35 sacks, pulled to 300', circulated with 80 sacks cement.

RECEIVED
DEC 16 2005
KCC WICHITA

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 401 West Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: Mar-Lou Oil Company
State of Kansas County, Ellsworth

Marlin B. Robinson (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Marlin B Robinson
(Address) P O Box 218, Wilson KS 67490

WILMA F. OLDS
Notary Public - State of Kansas
My Appt. Expires September 17, 2009

SUBSCRIBED and SWORN TO before me this 14 day of December, 2005
Wilma F. Olds My Commission Expires: Sept. 17, 2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

dm

Quality Well Service, Inc.

401 West Main
Lyons, KS 67554

Invoice

Date	Invoice #
12/12/2005	716

Bill To
Mar-Lou Oil Company Box 218 Wilson, KS 67490

RECEIVED
DEC 16 2005
KCC WICHITA

P.O. No.	Terms	Lease Name
		Louis Schartz

Description	Qty	Rate	Amount
Rig Time	14.5	155.00	2,247.50T
Trucking Floor		100.00	100.00T
Sand		35.00	35.00T
Cement	5	9.00	45.00T
Torch		50.00	50.00T
Torch-Cut surface off		50.00	50.00T
Water Truck	5	65.00	325.00T
Backhoe	4	65.00	260.00T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
Tubing Rental	1,300	0.50	650.00T
<p>12-6-05 Drove to location, moved pumping unit, raised pole, checked hole, sanded off bottom, loaded casing with water, cut tubing head off, had 6 inches casing. Drove home.</p> <p>12-9-05 Drove to location, checked hole, sand was at 3000', dumped 5 sacks cement with baler, had Perf-tech shoot holes at 1300', 900', 300'. Ran 1300' tubing, pumped 35 sacks cement, pulled to 900', pumped 35 sacks, pulled to 300', circulated with 80 sacks, pulled rest of tubing, tore down rig, cut casing head off 4' below ground, cleaned up location. Dug out north well - was plugged.</p>			
Subtotal			\$3,797.50
Sales Tax (6.3%)			\$239.24
Total			\$4,036.74