

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Mar-Lou Oil Company

Address: Box 218

Phone: (785) 658-2246 Operator License #: 33315

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)
by: Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-22-112-00-00

Lease Name: Isern

Well Number: 5

Spot Location (QQQQ): _____ - S2 - S2 - SW
2970 Feet from North / South Section Line
1320 Feet from East / West Section Line
Sec. 12 Twp. 20 S. R. 11 East West

County: Barton

Date Well Completed: _____
Plugging Commenced: 12-2-05
Plugging Completed: 12-6-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	227	
				5 1/2	3313	2200

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3260', baled 5 sacks cement, Ripped at 2410', 2200', pulled to 1300', pumped 90 sacks and 3# hulls, pulled to 450', pumped 40 sacks and 1# Hulls, pulled to 250', circulated with 75 sacks cement.

RECEIVED

DEC 16 2005

KCC WICHITA

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925


Address: 401 West Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: Mar-Lou Oil Company

State of Kansas County, Barton Ellsworth

Martin B. Robinson (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Martin B. Robinson
(Address) P O Box 218, Wilson, KS 67490



SUBSCRIBED and SWORN TO before me this 14 day of December, 2005

Wilma F. Olds My Commission Expires Sept 17, 2009
Notary Public

Bum

Quality Well Service, Inc.

**401 West Main
Lyons, KS 67554**

Invoice

Date	Invoice #
12/12/2005	717

Bill To
Mar-Lou Oil Company Box 218 Wilson, KS 67490

P.O. No.	Terms	Lease Name
		Isern #5

Description	Qty	Rate	Amount
Rig Time	20	155.00	3,100.00T
Trucking Floor		100.00	100.00T
Sand		35.00	35.00T
Cement	5	9.00	45.00T
Ripping Pipe	2	150.00	300.00T
Torch		50.00	50.00T
Water Truck	5.5	65.00	357.50T
Backhoe	4.5	65.00	292.50T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
Wiping Rubber		20.00	20.00T
12-2-05 Drove to location, raised pole, checked hole, sanded off bottom, loaded casing with water, moved pumping unit, drove home.			
12-5-05 Drove to location, checked hole, sand was at 3260', dumped 5 sacks cement with baler, dug cellar, unpacked casing head, set floor, pulled slips, cut surface pipe off. pulled stretch, had 16", ripped casing at 2410', worked pipe. Ripped casing at 2200', came free, pulled to 1300', swedged in, drove home.			
12-6-05 Drove to location, had to wait on cement trucks, pumped 90 sacks and 3# hulls at 1300', pulled to 450', pumped 40 sacks 1# hull, pulled to 250', circulated with 75 sacks cement, pulled rest of casing, tore down floor & rig, washed cement out of casing, cleaned up location.			
Subtotal			\$4,335.00

**RECEIVED
DEC 16 2005
KCC WICHITA**

Sales Tax (6.55%)	\$283.94
Total	\$4,618.94