

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-187-21039-0000

LEASE NAME FLOYD

WELL NUMBER 2-9R

660' FN Ft. from S Section Line

1250' FE Ft. from E Section Line

SEC. 9 TWP. 28S RGE. 40W (E) or (W)

COUNTY STANTON

Date Well Completed spud 10/04, not compl

Plugging Commenced 12/01/05

Plugging Completed 12/01/05

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # 072) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/05 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 3266' GL Bottom 2336' T.D. 3148'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2208'	2422'	8 5/8"	669'	0
				5 1/2"	3147'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

12/01/05 P&A witnessed by J Holland. Pmp 300# cshs w/ 12 bbl mud & 60 sx cmt plug frm 1961'-1431'. Pmped 17 bbl mud 1431'-700' & 80 sx cmt plug 700'-0'. Pmp 5 sx cmt 30'-0'. Cut 8 5/8" surf csg & 5 1/2" prod csg 3' bgl. Top of csg stub w/15 sx cement. Weld on trash cover - ID plate.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039



SWORN TO before me this 13th day of December, 2005

Angie G. Hernandez
Notary Public
My Commission Expires: 7-14-2009

Bm