

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Southern Star Central Gas Pipeline

Address: 4700 Ky. Hwy. 56 West, P.O. Box 20010 Owensboro, Ky. 42304

Phone: (270) 852-4490 Operator License #: 33097

Type of Well: Gas Storage Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 9/30/2005 (Date)

by: Clayton Titel (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Colony Ss. Depth to Top: 916' Bottom: 922' T.D. 922'

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 207-19351-00-01

Lease Name: Piqua Storage Field

Well Number: 0-2

Spot Location (QQQQ): \_\_\_\_\_ - \_\_\_\_\_ - NW - SW

1960' Feet from ☐ North / ☒ South Section Line

4302' Feet from ☒ East / ☐ West Section Line

Sec. 3 Twp. 25 S. R. 17 ☒ East ☐ West

County: Woodson

Date Well Completed: 7/1/1924 original

Plugging Commenced: 11/14/2005

Plugging Completed: 11/15/2005

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records |                 | Casing Record (Surface Conductor & Production) |      |      |         |            |
|---------------------------|-----------------|--|------|------|---------|------------|
| Formation                 | Content         | From   | To   | Size | Put In  | Pulled Out |
| Colony Ss.                | gas observation | 0  | 11'  | 10"  | NA      |            |
|                           |                 | 0  | 916' | 2"   | 30 sks. |            |
|                           |                 |  |      |      |         |            |
|                           |                 |  |      |      |         |            |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

11/14/2005 Ran 1" to 916' in 2" casing. Pumped 30 sks. Type A cement in 2" and washed 1" down backside to 500', pulled out 1".

11/15/2005 Washed 1" down in 2" to 660', washed 1" down backside to 630', pumped 307 sks. of Type A cement to surface.

11/16/2005 Ran 1" to 40' inside 2", ran 1" to 20' on backside of 2", pumped 30 sks. cement to surface. Total: 367 sks. Type A cement.

Casing cut 4' below surfaced and capped.

Name of Plugging Contractor: Splane Pulling & Roustabout Service License #: 6372

Address: P.O. Box 386 Chanute, Kansas 66720

Name of Party Responsible for Plugging Fees: Southern Star Central Gas Pipeline

State of Kentucky County, Daviess, ss.

D. Mark Rouse

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) D. Mark Rouse

(Address) SSCGP P.O. Box 20010

SUBSCRIBED and SWORN TO before me this 6th day of December, 20 05

Elizabeth A Morris My Commission Expires: 7/29/06  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

DEC 12 2005  
12-12-05  
KCC WICHITA

Bum