

9-22

6 031169

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION N/2 NE SW, SEC. 2, T 7 S, R 21 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,488 -00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 7076

Operator: Black Diamond Oil Inc.  
Name & Address: 1105 East 30th Suite 4  
Hays, Ks. 67601

2310 feet from S section line  
3300 feet from E section line

Lease Name Pruitt Well # 1  
County Graham 121.88  
Well Total Depth 3750 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Oper License Number 8241

Address Russell, Ks.

Company to plug at: Hour: AM Day: 22 Month: Sept Year: 19 88

Plugging proposal received from Jack Fox

(company name) Emphasis (phone)

were: 8 5/8" set at 220' w/150 sks cwc. Circ. hole w/no less than 36 vis.

mud w/no loss or gain in fluid. Balance all plugs w/mud, keep hole full. Order 190 sks

60/40 Poz 6% 3% 8 5/8" wiper plug. Allied Cement Co.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 21 1988

10-21-88

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:00AM Day: 22 Month: Sept Year: 19 88

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe at 1825' w/25 sks  
1100' w/100 sks and Hulls  
270' w/40 sks  
40' w/10 sks wiper plug.  
15 sks in rathole.

Remarks: Anhy 1805' - 35' Elev. 2230'  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Do not reserve this plugging.

DATE 10-24-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 22661

Carl Goodrow