

4 050078

12-16

16R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,611-00-00

N/2 N/2, SEC. 1, T. 7, S. R. 21 W/E xx

2310 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Trexler Well # 6

Operator: Ritchie Expl. Inc.

County Graham 119.92

Name & Address 125 N. Market Suite 1000

Well Total Depth 3690 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

316-267-4375

Surface Casing: Size 8 5/8 feet 202

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 6033

Address

Company to plug at: Hour: PM Day: 16 Month: Dec. Year: 19 90

Plugging proposal received from Lloyd Delette

(company name) (phone)

were: Order 215 sks 60/40 poz 6% gel w/1/4 lb. f.c. per sk. and 8 5/8 wiper plug.

Spot all pugs through drill pipe w/heavymud between all plugs.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 6:15PM Day: 16 Month: Dec. Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 3600 w/25 sks

2nd plug 1780 w/25 sks

3rd pug 985 w/00 sks

4th plug 255 w/40 sks

5th plug 40' w/10 sks and 8 5/8 wiper plug.

15 sks in rathole.

Remarks: Cemented by Allied. Elevation 2160 Anhy6 1769 - 1801 Arb. 3663

If additional description is necessary, use BACK of this form.)

INVOICED

(operator did not) observe this plugging.

DATE 2-7-91

INV. NO. 30577

E.S.

Signed Marvin D. Miller (TECHNICIAN) Marvin Miller