

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22464-00 <sup>02-ab-5-29</sup>  
Spot: NENWNW Sec/Twnshp/Rge: 7-7S-21W  
4950 feet from S Section Line, 4320 feet from E Section Line  
Lease/Unit Name: ANITA DAVIS Well Number: 1  
County: GRAHAM Total Vertical Depth: 3764 feet

Operator License No.: 4767  
Operator Name: RITCHIE EXPLORATION, INC.  
Address: BOX 783188  
WICHITA, KS 67278 11/13

Conductor Pipe: Size feet:  
Surface Casing: Size 8.62 feet: 217 170 SX CMT  
Production: Size 4.5 feet: 3742 125 S XCMT 122,33  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/13/2000 12:00 PM

Plug Co. License No.: 4767 Plug Co. Name: RITCHIE EXPLORATION, INC.

Proposal Rcvd. from: PETER J. FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (785) 691-9500

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 800# hulls.

Plugging Proposal Received By: HUBERT DEINES  
Date/Time Plugging Completed: 11/13/2000 11:00 AM

Witness Type: Plugging Operations Partially Witnessed  
KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 217' w/170 sxs cwc.  
4 1/2" set at 3742' w/125 sxs.  
D.V. at 1824' w/445 sxs cwc.  
Prod Perfs 3364' - 3735'.  
Squeezed 4 1/2" w/200 sxs cement blend w/800# hulls mixed in to Max. P.S.I. 1000#. S.I.P. 800#.  
Squeezed 8 5/8" w/10 sxs cement blend to Max. P.S.I. 300#. Held.  
Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 2000  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Carl Goodrow  
(TECHNICIAN)

INVOICED  
DATE 12/1/00  
INVOICE NO. 2001061

Form CP-2/3

NOV 21 2000

replacement card

Property of **WILDCAT** Ks Corp Comm

RITCHIE EXPLORATION  
WICHITA KS 67202

7-07S-21W  
4950'FSL & 4320'FEL, SEC

# 1 DAVIS, ANITA OWWO

site: 5 N & 4-3/4 W OF NICODEMUS KS  
contr: UNKNOWN

cty: GRAHAM  
field: WC (ANITA DISC)

API 15-065-22464-00-01

geol:  
date 01/29/96    spd date 06/19/95    drlg comp 06/19/95    card issued 01/29/96    last revised 12/02/96

•			

ELV: 2215 KB, 2210 GL LOG

tops.....	depth/datum
ANH.....	1830 + 385
B/ANH.....	1861 + 354
TOP.....	3203 - 988
HEEB.....	3407 - 1192
TOR.....	3429 - 1214
LANS.....	3446 - 1231
BKC.....	3637 - 1422
CONG SD.....	3685 - 1470
PBTD.....	3688 - 1473
ARB ERO.....	3716 - 1501
ARB.....	3731 - 1516
LTD OLD.....	3764 - 1549
RTD OLD.....	3764 - 1549

IP status:  
OIL, P 3.80 BO & 169 BWP, SHAW 3430-3432, LKC  
3446-3633 OA, 06/29/95  
INFO REL: 12/2/96 - IP & COMP INFO  
NOTE: INFO REL 3/21/90 - WAS OIL WELL - TIGHT  
HOLE  
OLD INFO: OPERATOR WAS RITCHIE EXPLORATION,  
1 DAVIS, ANITA, SPD 06/06/88, 06/13/88 8-5/8" 217 /  
170 SX, 4-1/2" 3742 / 125 SX, OIL, P 30 BO & 30 BWP,  
LKC 3515-3604 OA, 06/28/88 (CARD ISSUED 10/12/88)  
CONTR: MURFIN DRILLING  
GEOL: BOB MATHIESEN

COPYRIGHT 1996  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)