

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22863-00-00  
Spot: N2S2N2, Sec/Twnshp/Rge: 4-7S-21W  
1600 feet from N Section Line, 2520 feet from W Section Line  
Lease/Unit Name: MCKISSON Well Number: 1  
County: GRAHAM Total Vertical Depth: 3600 feet

Operator License No.: 9449  
Op Name: GREAT EASTERN ENERGY & DEV. CO  
Address: 550 W. TEXAS STE 660  
MIDLAND, TX 79702

Production Casing Size: 5.5 feet: 3755 175 SX CMT  
Surface Casing Size: 8.625 feet: 237 165 SX CMT

*B* 117.00

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/28/2003 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTY ANDREW Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Top of cement 3100'.  
Perfs 3434' - 3453'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/28/2003 1:00 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

Mike's Testing & Salvage sanded back bottom 3350' and topped with 5 sxs cement.  
Shot casing at 1770' - pulled 5' sub to 1765' - pumped 130 sxs 60/40 pozmix with 300# hulls.  
Pulled casing to 1000' - pumped 40 sxs 60/40 pozmix with 200# hulls.  
Pulled casing to 150' - pumped 30 sxs 60/40 pozmix.  
Pulled casing and topped off with 10 sxs.  
Hole was standing full.

RECEIVED  
MAY 01 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #11153.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 5-2-03

INV. NO. 2003061483

APR 29 2003