

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,395 0000

LEASE NAME Lorena

WELL NUMBER 1

990 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 3 TWP. 7S RGE. 21 ~~(XXXXX)~~(W)

COUNTY Graham

Date Well Completed 8-11-87

Plugging Commenced 8-11-87

Plugging Completed 8-12-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Marmik Oil Company

ADDRESS 200 N. Jefferson, #500, El Dorado, AR 71730

PHONE# (501) 862-8546 OPERATORS LICENSE NO. 6875

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District 6 Ed Schumacher

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3794

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	220	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pump mud to 3700' set 1st plug from 3700' to 3620' w/20 sx; pump mud to 1820' set 2nd plug from 1820' to 1740' w/20 sx; pump mud to 990' set 3rd plug from 990' to 590' w/100 sx and 1 sx Floseal; pump mud to 265' set 4th plug from 265' to 104' w/40 sx; pump mud to 40' set 5th plug w/wiper plug and 10 sx from 40' to surface. Pump 10 sx in rathole. All cement 60/40 posmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.


Jack K. Wharton

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 14th day of August, 19 87



Commission Expires: Dec. 29, 1990

Janet A. Stuck
Notary Public

AUG 17 1987

8-17-87

STATE CORPORATION COMMISSION
Wichita, Kansas