

15-191-01023-00-00

Form CP-4


STATE OF KANSAS
STATE-CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sumner County, Sec. 22 Twp. 34S Rge. (E) 3 (W)

Location as "NE/CNW/SW" or footage from lines NW SW SW
Lease Owner Herndon Drilling Co.
Lease Name A. Subera Well No. 3
Office Address Box 489 Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 6-21 19 57
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 7-12 19 63
Plugging completed 7-12 19 63
Reason for abandonment of well or producing formation
If a producing well is abandoned, date of last production 1-31 19 63
Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Howard Hess
Producing formation Simpson sand Depth to top 4722' Bottom 4732' Total Depth of Well 4732 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill open hole W/gravel from 4732' to 4718'. Dump 4 sacks cement W/dump bailer. Set 5' rock bridge at 40'. Dump 4 sacks cement. Fill W/mud to within 18' of top. Dump 5' rock bridge & 5 sacks cement on top.

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Winfield Oil Field Ser. Inc.
Address Box 952 Winfield, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Seth Herndon, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Seth Herndon, Jr.
Box 489, Tulsa, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of August, 1963

My commission expires June 19, 1965

Johnnie Alene Frese
Johnnie Alene Frese Notary Public.



15-191-01023-0000
P

WELL LOG ON A. SUBERA NO. 3

Spudding date: 5/22/57
Date casing set: 5/24/57
Date rotary completed: 6/15/57
Date cable completed:

Location:

NW SW SW, Section 22-34S-3W, Sumner County, Kansas

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>	<u>REMARKS</u>
0	100	Shale	
100	652	Shale & Shells	
652	2735	Lime & Shale	
2735	2915	Lime	
2915	3115	Lime & Shale	
3115	3235	Sand & Shale	
3235	3650	Lime & Shale	
3650	3720	Lime	
3720	4135	Lime & Shale	
4135	4195	Lime	
4195	4325	Lime & Shale	
4325	4417	Lime & Chert	
4417	4593	Lime	
4593	4625	Lime & Chert	
4625	4652	Lime	
4652	4728	Lime & Shale	
4728	4732	Sand	
4732		Total Depth	

Ran 20 Jts. 8-5/8" 24# Casing - set at 652' and cemented w/500 Sx. Pozmix w/ 2% C.C.

Ran 143 Jts. 5 1/2" 14# J-55 Casing - set @ 4722' and cemented w/175 Sx. Pozmix. D V Tool set @ 1550' and cemented w/275 Sx. w/3% Gel.

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1963

CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me this 20th day of June, 19 57

I certify the above and foregoing to be a true and exact copy of the original driller's log on the A. Subera #3.

HERNDON DRILLING COMPANY

[Signature]
Notary Public
My commission expires: 1-27-60

By: [Signature]
Title: Assistant Secretary