

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 600 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-065-22,444-00-00
 LEASE NAME Holsman 31-2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div. office within 30 days.

WELL NUMBER 1
 4240' FSL Ft. from S Section Line
 2310' FEL Ft. from E Section Line
 SEC. 2 TWP. 7S RGE. 21 (or (W))
 COUNTY Graham
 Date Well Completed 3-26-88
 Plugging Commenced 3-26-88
 Plugging Completed 3-26-88

EASE OPERATOR PanCanadian Petroleum Company
 ADDRESS 600 17th St. 1800 So. Tower Denver, CO 80202

PHONE# (303) 825-8371 OPERATORS LICENSE NO. 8000
 Character of Well D & A

Oil, Gas, D&A, SWD, Input, Water Supply Well

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Hays, Ks. Dist. 6 State Plugger Gilbert Leiker

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top 3850' Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 311' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
1st plug 3725' to 3625' w/25sx; pump mud to 1880'; 2nd plug 1880' to 1480' w/100sx, 1sx floccel, pump mud to 340'; 3rd plug 340' to 180' w/40sx, pump mud to 40'; 4th plug 40' to surface w/10sx. Rathole 10sx; 60-40 posmix, 6% gel, 3%cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No.


Address 801 Union Center Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) Jack K. Wharton
 (Address) 801 Union Center Wichita, KS

SUBSCRIBED AND SWORN TO before me this 29th day of March, 19 88



James A. Stuck
 NOTARY PUBLIC

My Commission Expires: 12-29-90

