

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,464 ⁰²

LEASE NAME Anita Davis

WELL NUMBER 1

4950 Ft. from S Section Line

4320 Ft. from E Section Line

SEC. 7 TWP. 7 RGE. 21W (E) or (W)

COUNTY Graham

Date Well Completed 11/10/00

Plugging Commenced 11/10/00

Plugging Completed 11/13/00
11/10/00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS P.O. Box 783188

PHONE# (316) 691-9500 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/10/00 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? no If not, Is well log attached? yes

Producing Formation Lansing Depth to Top 3446' Bottom 3633' T.D. 3764'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Toronto	Oil & Brine	3429'	3446'			
Lansing/KC	Oil & Brine	3446'	3637'	8 5/8"	217'	None
Arbuckle	Brine	3730'	3738'	4 1/2"	3742'	None
Oread	Brine	3203'	3407'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped 10 sacks 60/40 Pozmix cement with 10% gel down 8 5/8" surface casing. Shut in at 300#. Pumped 200 sacks 60/40 Pozmix cement with 10% gel and 800# hulls down 4 1/2" casing. Shut in at 800#. Plugging complete.

(If additional description is necessary, use BACK of this form.) **RECEIVED**
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor Allied Cementing, Inc. License No. _____

Address P.O. Box 31, Russell, KS 67665

JAN 02 2001

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc. CONSERVATION DIVISION

STATE OF Kansas COUNTY OF Sedgwick, ss. WICHITA, KS

Ritchie Exploration, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 783188, Wichita, ks

SUBSCRIBED AND SWORN TO before me this 27th day of December, 19 2000

KAREN HOPPER
Notary Public - State of Kansas
My Appt. Expires 10/27/03

My Commission Expires: 10/27/03 Karen Hopper Notary Public