

15-065-30192-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Graham County. Sec. 6 Twp. 7 Rge. 21 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SW SW SW  
Lease Owner Dene E. Pratt Oil Operations  
Lease Name Ridgley Well No. 1  
Office Address P.O. Box # 370 Hays, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 8-31-1966  
Application for plugging filed 8-31-1966  
Application for plugging approved 8-31-1966  
Plugging commenced 8-31-1966  
Plugging completed 8-31-1966  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Bill Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3795' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE PIPE				8-5/8"	202'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with rotary mud to a depth of 540' where 1st plug was set using 20 sax cement.  
Filling hole with rotary mud to a depth of 200' where 2nd plug was set using 18 sks cement.  
Rotary mud was used to fill hole to a depth of 40' where 3rd plug was set using 10 sks.  
cement and filling hole to surface.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 6 1966

9-6-66

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.  
Address Route # 2 Victoria, Kansas

STATE OF KANSAS, COUNTY OF ELLIS, ss.  
I, Leo F. Dreiling (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
LEO F. DREILING  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of September, 19 66

My commission expires October 26, 1968

[Signature]  
Elmer Weltz  
Notary Public.

L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

15-065-30192-00-00

WELL LOG

Company DON E PRATT OIL OPERATIONS  
HAYS, KANSAS

Sec. 6 Twp. 7 Rng. 21

Farm Ridgley No. # 1

Location SW-SW-SW

Total Depth 3795'

County Graham  
2238' K.B.

Comm. 8-24-66 Comp. 8-31-66

Elevation: 2235' D. F.

Contractor L.J.Dreiling & Sons, Inc.  
Victoria, Kansas

2233' G. R.

Casing Record

Cement Record

Production:

202' 8-5/8"

100 sax

D & A

Figures Indicate Bottom of Formations

0'	189'	Top Soil-Blue Shale
189'	208'	Blue Shale
208'	1178'	Shale
1178'	1363'	Shale & Red Bed
1363'	1576'	Sand
1576'	1842'	Red Bed & Shale
1842'	1868'	Anhy.
1868'	1875'	Anhy.
1875'	2245'	Shale
2245'	2450'	Shale
2450'	2490'	Lime & Shale
2490'	2650'	Shale & Lime
2650'	2887'	Shale & Lime Streaks
2887'	2960'	Lime & Shale
2960'	3100'	Shale & Lime
3100'	3295'	Lime & Shale
3295'	3354'	Lime & Shale
3354'	3435'	Lime
3435'	3512'	Lime
3512'	3523'	Lime
3523'	3560'	Lime
3560'	3645'	Lime
3645'	3670'	Lime
3670'	3718'	Lime
3718'	3789'	Lime
3789'	3795'	Lime
3795'	T.D.	

STATE OF KANSAS)  
                                  )ss  
COUNTY OF ELLI\$

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Ridgley # 1.

RECEIVED

*Leo F. Dreiling*  
LEO F. DREILING

Subscribed and sworn to before me this 1st day of Sept. 1966

*Emer Welch*  
NOTARY PUBLIC

My commission expires: October 26, 1968

9-6-66