

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19547-00-00
Spot: SENENE Sec/Twnshp/Rge: 17-27S-6E
4048 feet from S Section Line, 530 feet from E Section Line
Lease Name: MACLEAN Well #: 1
County: BUTLER Total Vertical Depth: 3119 feet

Operator License No.: 6655
Op Name: CRAWFORD, GARRY F. DBA CRAWFO
Address: PO BOX 727
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3104	0	
SURF	8.625	53	0	

#101 37

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2005 8:00 AM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: GARRY CRAWFORD Company: CRAWFORD PRODUCTION COMP Phone: (316) 321-3942

Proposed Plugging Method: Sand back to 2886', dump 5 sxs cmt w/ dump bailer. Perf 4-1/2" csg @ 250' & circ cmt to surf.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 09/30/2005 12:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Sanded back to 2886' and dump bailed 5 sacks of cement on top. Perforated 4-1/2" casing at 250' and established circulation. Pumped 44 sacks of 60/40 posmix with 4% gel and 3% cc to surface.

United Cementing #6988
field ticket #6239


Perfs: **RECEIVED
KCC DISTRICT #2
DEC 14 2005
WICHITA, KS**

Remarks: VIOLA OPEN HOLE 3104' - 3119'

Plugged through: TBG

**RECEIVED
JAN 03 2006
KCC WICHITA**

District: 02

Signed 
(TECHNICIAN)

INVOICED
DATE 1-3-06
INV. NO. 2006060928