

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20539-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 35-31S-4E
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: E L MORRIS Well #: 1B
County: COWLEY Total Vertical Depth: 3410 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3404	900	65 SX CMT
SURF	8.625	201	0	135 SX CMT

83
\$110

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2005 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 438-2856

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 09/30/2005 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

9/8/2005 -- Bottom plug; RIH with tubing at 3300'; and circulated hole clean. Sanded back to 3330; dump bail; and put 5 sacks of cement on top.
9/9/2005 -- RIH with tubing at 225'. Copeland Acid mixed and pumped 125 sacks of 60/40 posmix with 4% gel to surface. POOH with tubing and topped off 4-1/2" casing with 25 sacks of 60/40 posmix with 4% gel to surface.

Copeland #26148

Perfs:

Top	Bot	Thru	Comments
3404	3410		

RECEIVED
KCC DISTRICT #2
DEC 14 2005
WICHITA, KS


RECEIVED
JAN 03 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED
DATE 1-3-06
INV NO 2006060924