

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Rama Operating Co., Inc.
 Address: P.O. Box 159 Stafford, Ks. 67578
 Phone: (620) 234-5191 Operator License #: 3911
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: Butch Hoberecht (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (if needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-095-21664-00-00
 Lease Name: Milburn "A"
 Well Number: 1
 Spot Location (QQQQ): SW-SW-SW
330 Feet from North / South Section Line
330 Feet from East / West Section Line
 Sec. 13 Twp. 27 S. R. 10 East West
 County: Kingman
 Date Well Completed: _____
 Plugging Commenced: 12-20-05
 Plugging Completed: 12-22-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	319	none
				5-1/2"	4497	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 4230' and dumped 5 sacks of cement with bailer, cut casing at 2200'. Pulled casing to 1400', mixed 200 # hull and 35 sacks of cement, 60/40 pos, 4% gel at 1400', pulled up to 950' and mixed 35 sacks of cement, pulled to 370' and circulated cement to surface with 135 sacks of cement. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
 Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Rama Operating Co, Inc.
 State of Kansas County, Rice, ss.


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso
 (Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 30th day of December, 20 05

Irene Herzberg
 Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JAN 03 2006
KCC WICHITA

sun